

-3-

Exterior Lines, T 6 S R 33 E., W. M.

Chains	
	S.89°46'E. on true line bet. Secs. 2 & 35. Var.19°E.
	Ascend abruptly.
2.2.50	Brook, 2 lks. wide, runs N.W.
40.00	A point, 600 ft. above Sec. Cor. Set granite stone, 20 x 13 x 5 ins., 15 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face, from which A tamarack, 30 ins. diam., brs. S.10°W., 27 lks. dist., marked ¼ S B T. A tamarack, 30 ins. diam., brs. N.23°E., 20 lks. dist., marked ¼ S B T.
65.00	Top of mountain, course N.W. & S.E. Descend.
80.00	A point, 200 ft. below summit. Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor to Secs. 1, 2, 35 & 36, marked T 6 S S 36 on N.E. R 35 E S 1 on S.E. T 7 S S 2 on S.W. S 35 on S.W. faces, with 1 notch on E. and 5 notches on W. edges, from which A fir, 10 ins. diam., brs. N.60°E., 26 lks. dist., marked T 6 S R 33 E S 36 B T. A fir, 10 ins. diam., brs. S.42°E., 17 lks. dist., marked T 7 S R 33 E S 1 B T. A fir, 10 ins. diam., brs. S.38°W., 20 lks. dist., marked T 7 S R 33 E S 2 B.T. A spruce, 24 ins. diam., brs. N.50°W., 14 lks. dist., marked T 6 S R 33 E S 35 B T.
	Land; mountainous.
	Soil; 3rd rate.
	Densely covered with forests of pine, fir & spruce & tam- arack, 80 chs.