

## Exterior Lines, T 6 S R 33 E., W. M.

Chains	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> S on W. face, from which</p> <p>A fir, 10 ins. diam., brs. S.88°E., 28 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p>A fir, 10 ins. diam., brs. S.60°W., 13 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p>
60.50	Brook, 4 lks. wide, runs W.
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 6, 7, 1 &amp; 12, marked</p> <p>T 6 S S 6 on N.E.</p> <p>R 34 E S 7 on S.E.</p> <p>R 33 E S 12 on S.W. and S 1 on N.W. faces, with 1 notch on N. and 5 notches on S. edges,</p> <p>from which</p> <p>A pine, 10 ins. diam., brs. S.38°E., 28 lks. dist., marked T 6 S R 34 E S 7 B T.</p> <p>A pine, 30 ins. diam., brs. N.22°E., 28 lks. dist., marked T 6 S R 34 E S 6 B.T.</p> <p>A tamarack, 10 ins. diam., brs. S.41°W., 15 lks. dist., marked T 6 S R 33 E S 12 B T.</p> <p>A pine, 10 ins. diam., brs. N.65°W., 11 lks. dist., marked T 6 S R 33 E S 1 B T.</p>
	Land; mountainous.
	Soil; 2nd rate.
	Densely covered with forests of pine, fir, spruce & tamarack 80 chains.
	N. bet. Secs. 1 & 6.
	Var. 19°E.
	Ascend.
30.00	Ridge, 300 ft. high, course E. & W.
40.00	<p>Set basalt stone, 13 x 8 x 8 ins., 8 ins. in ground; for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on W. face, from which</p>