

Subdivisional Lines, T. 6 S., R. 33 E., W. M.

Chains	
80.00	<p>Thence gently descend.</p> <p>To point, 200 ft. below $\frac{1}{4}$ Sec. Cor. and</p> <p>Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 13, 14, 23 & 24, marked</p> <p style="padding-left: 40px;">T 6 S S 13 on N.E. R 33 E S 24 on S.E. S 14 on N.W. and S 23 on S.W. faces, with 3 notches on S. and 1 notch on E. edges,</p> <p>from which</p> <p style="padding-left: 40px;">A spruce, 10 ins. diam., brs. N.46°E., 13 lks. dist., marked T 6 S R 33 E S 13 B T.</p> <p style="padding-left: 40px;">A tamarack, 20 ins. diam., brs. S.49°E., 9 lks. dist., marked T 6 S R 33 E S 24 B T.</p> <p style="padding-left: 40px;">A spruce, 10 ins. diam., brs. S.18°W., 11 lks. dist., marked T 6 S R 33 E S 23 B T.</p> <p style="padding-left: 40px;">A spruce, 10 ins. diam., brs. N.79°W., 14 lks. dist., marked T 6 S R 33 E S 14 B T.</p> <p>Land; rolling.</p> <p>Soil; good 2nd rate.</p> <p>Densely covered with forests of pine, fir, spruce & tamarack timber, 80.00 chs.</p> <p>Thick undergrowth of alder & small pine, 80 chs.</p>
40.00	<p>E. on random line bet. Secs. 13 & 24.</p> <p style="text-align: right;">Var. 19°E.</p> <p>Over rolling hillside, facing N.E.</p> <p>To a point, 200 ft. below last Sec. Cor. and</p> <p>Set temp. $\frac{1}{4}$ Sec. Cor.</p>
44.00	Descend abruptly to
50.00	Foot of descent, spring branch, 5 lks. wide, course N.E.
79.92	<p>Intersect E. Bdy. of Tp. at Cor. to Secs. 13, 18, 19 & 24, which is a post, 4 ins. sq., firmly set in ground, marked</p> <p style="padding-left: 40px;">T 6 S S 18 on N.E. R 34 E S 19 on S.E.</p>