

Subdivisional Lines, T 6 S R 33 E W M.

Chains

- 79.97 Intersect E. Bdy. of Tp. at Cor. to Secs. 1, 6, 7 & 12,
which is a post, 4 ins. sq., firmly set in ground,
marked .
- T 6 S S 6 on N.E.
R 34 E S 7 on S.E.
R 33 E S 12 on S.W.
S 1 on N.W. faces, with
1 notche on N. and
5 notches on S. edges,
from which
- A pine, 10 ins. diam., brs. S.38°E., 28 lks. dist.,
marked T 6 S R 34 E S 7 B T.
A pine, 30 ins. diam., brs. N.22°E., 28 lks. dist.,
marked T 6 S R 34 E S 6 B T.
A tamarack, 10 ins. diam., brs. S.41°W., 15 lks. dist.,
marked T 6 S R 33 E S 12 B T.
A pine, 10 ins. diam., brs. N. 65° W., 11 lks. dist.,
marked T 6 S R 33 E S 1 B T.
- Thence I run .
- W. on true line bet. Secs. 1 & 12, with same Var.
- 39.98 Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground,
for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on N. face, from which
- A tamarack, 20 ins. diam., brs. S.62°E., 22 lks. dist.,
marked $\frac{1}{4}$ S B T.
A pine, 10 ins. diam., brs. N.42°W., 18 lks. dist.,
marked $\frac{1}{4}$ S B T.
- 79.97 The Cor. to Secs. 1, 2, 11 & 12.
Land; hilly.
Soil; 2nd rate.
Densely covered with forests of pine, spruce & tamarack,
79.97 chs.
Thick undergrowth of balm, willow, small pine, spruce &
tamarack, 79.97 chs.
-
- N. bet. Secs. 1 & 2.