

Subdivisional Lines, T 6 S R 33 E W M.

Chains

A basalt stone, 14 x 12 x 8 ins., 9 ins. in ground, for Closing Cor. to Secs. 2 & 3, marked C.C. with 2 notches on E. and 4 notches on W. edges, from which

A pine, 10 ins. diam., brs. S.29°E., 37 lks. dist marked T 6 S R 33 E S 2 B T.

A pine, 6 ins. diam., brs. S.8°W., 38 lks. dist., marked T 6 S R 33 E S 3 B T.

Land; rolling.

Soil; 1st & 2nd rate.

Densely covered with forests of pine, fir, spruce and tamarack timber, 75.71 chs.

Undergrowth of balm & pine, 75.71 chs.

From the Cor. to Secs. 3, 4, 33 & 34, on S. Bdy. of Tp., which is a post, 4 ft. long, 4 ins. sq., firmly set in ground, marked

T 6 S S 34 on N.E.

R 33 E S 3 on S.E.

T 7 S S 4 on S.W. and

S 33 on N.W. faces, with

3 notches on E. & W. edges,

from which

A fir, 20 ins. diam., brs. N.81°E., 38 lks. dist., marked T 6 S R 33 E S 34 B T.

A fir, 10 ins. diam., brs. S.9°E., 102 lks. dist., marked T 7 S R 33 E S 3 B T.

A tamarack, 30 ins. diam., brs. S.17°W., 80 lks. dist., marked T 7 S R 33 E S 4 B T.

A pine, 36 ins. diam., brs. N.10°W., 62 lks. dist., marked T 6 S R 33 E S 33 B T.

I run

N. bet. Secs. 33 & 34.

Var. 20°E.

Ascend over rolling ground.

40.00 Set spruce post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face, from which