

Subdivisional Lines, T 6 S R 33 E W M.

Chains

68.00 Top of mountain divide, course E. & W.
 80.00 Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground,
 for Cor. to Secs. 21, 22, 27 & 28, marked
 T 6 S S 22 on N.E.
 R 33 E S 27 on S.E.
 S 28 on S.W. and
 S 21 on N.W. faces, with
 2 notches on S. and
 3 notches on E. edges,
 from which
 A pine, 10 ins. diam., brs. N.60°E., 33 lks. dist.,
 marked T 6 S R 33 E S 22 B T.
 A pine, 13 ins. diam., brs. S.18°E., 16 lks. dist.,
 marked T 6 S R 33 E S 27 B T.
 A spruce, 8 ins. diam., brs. S.65°W., 16 lks. dist.,
 marked T 6 S R 33 E S 28 B T.
 A pine, 4 ins. diam., brs. N.42°W., 21 lks. dist.,
 marked T 6 S R 33 E S 21 B T.
 Land; mountainous.
 Soil; 2nd rate.
 Densely covered with forests of pine, fir, spruce & tam-
 arack, 80 chs.
 Thick undergrowth of pine, spruce & balm, 80 chs.

E. on random line bet. Secs. 22 & 27.

Var. 20°30'E.

1.50 Head of ravine, course N.W.
 20.00 Descend ridge, course N.E. & S.W.
 40.00 Set temp. $\frac{1}{4}$ Sec. Cor.
 69.00 Foot of hill & enter level bottom, course N. & S.
 79.00 Cable creek, 6 lks. wide, course N.
 79.60 Intersect N. & S. line, 20 lks. N. of Cor. to Secs. 22,
 23, 26 & 27,

Thence I run

N.89°51'W. on true line bet. Secs. 22 & 27.

With same Var.