

## Subdivisional Lines, T 6 S R 33 E W M.

Chains	
	N. bet. Secs. 15 & 16.
	Var. 19° 10' E.
	Descend.
40.00	Set fir post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face, from which A fir, 10 ins. diam., brs. N. 79° E., 4 lks. dist., marked $\frac{1}{4}$ S B T. A tamarack, 10 ins. diam., brs. N. 48° W., 11 lks. dist., marked $\frac{1}{4}$ S B T.
46.00	Ravine, course N.W.
80.00	Set basalt stone, 16 x 10 x 10 ins., 10 ins. in ground, for Cor. to Secs. 9, 10, 15 & 16, marked with 4 notches on S. and 3 notches on E. edges, from which A pine, 10 ins. diam., brs. N. 68° E., 9 lks. dist., marked T 6 S R 33 E S 10, B.T. A spruce, 8 ins. diam., brs. S. 65° E., 4 lks. dist., marked T 6 S R 33 E S 15 B T. A pine, 8 ins. diam., brs. S. 40° W., 2 lks. dist., marked T 6 S R 33 E S 16 B T. A pine, 10 ins. diam., brs. N. 63° W., 9 lks. dist., marked T 6 S R 33 E S 9 B T.
	Land; mountainous.
	Soil; 2nd rate.
	Densely covered with forests of pine, fir, spruce & tamarack, 80 chs.
	Thick undergrowth of small pine, fir & tamarack, 80 chs.
	E. on random line bet. Secs. 10 & 15.
	Var. 22° E.
7.50	Creek, 10 lks. wide, course N.W.
	Descend hill, course N.W. & S.E.
12.00	Trail, course N.W. & S.E.
34.00	Top of hill, course N.W. & S.E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
	Descend over rolling ground.