

Subdivisional Lines, T 6 S R 33 E W M.

Chains	
	Thick undergrowth of small pine, balsam & spruce, 73.13 chs.
	From the Cor. to Secs. 4, 5, 32 & 33, on S. Bdy. of Tp., which is a granite stone, 16 x 13 x 12 ins., firmly set in ground, marked with 4 notches on E. and 2 notches on W. edges, from which
	A pine, 10 ins. diam., brs. N.62°E., 55 lks. dist., marked T 6 S R 33 E S 33 B T.
	A fir, 10 ins. diam., brs. S.60°E., 88 lks. dist., marked T 7 S R 33 E S 4 B T.
	A fir, 10 ins. diam., brs. S.47°W., 15 lks. dist., marked T 7 S R 33 E S 5 B T.
	A pine, 20 ins. diam., brs. N.15°W., 56 lks. dist., marked T 6 S R 33 E S 32 B T.
	I run
	N. bet. Secs. 32 & 33.
	Var. 20°30'E.
40.00	Set granite stone, 18 x 10 x 10 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which
	A pine, 24 ins. diam., brs. S.62°E., 49 lks. dist., marked $\frac{1}{4}$ S B T.
	A tamarack, 12 ins. diam., brs. N.33°E., 20 lks. dist., marked $\frac{1}{4}$ S B T.
64.00	Brook, 2 lks. wide, course W.
80.00	Set pine post, .4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 28, 29, 32 & 33, marked
	T 6 S S 28 on N.E.
	R 33 E S 33 on S.E.
	S 32 on S.W. and
	S 29 on N.W. faces, with
	1 notch on S. and
	4 notches on E. edges,
	from which
	A pine, 30 ins. diam., brs. N.25°E., 27 lks. dist., marked T 6 S R 33 E S 28 B T.