

Subdivisional Lines, T 6 S R 33 E W M.

| Chains | |
|--------|--|
| 30.00 | Trail, course E& W. |
| 32.00 | Top of hill, course E. & W. |
| 40.00 | Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face, from which A pine, 10 ins. diam., brs. S.30°W., 10 lks. dist., marked $\frac{1}{4}$ S B T. A pine, 5 ins. diam., brs. N.65°E., 20 lks. dist., marked $\frac{1}{4}$ S B T. |
| 61.40 | Ravine, course W. |
| 80.00 | Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 19, 20, 29 & 30, marked T 6 S S 20 on N.E. R 33 E S 29 on S.E. S 30 on S.W. and S 19 on N.W. faces, with 2 notches on S. and 5 notches on E. edges, from which A pine, 12 ins. diam., brs. N.44°E., 38 lks. dist., marked T 6 S R 33 E S 20 B T. A tamarack, 8 ins. diam., brs. S.58° E., 20 lks. dist., marked T 6 S R 33 E S 29 B T. A fir, 10 ins. diam., brs. S.68°W., 32 lks. dist., marked T 6 S R 33 E S 30 B T. A pine, 8 ins. diam., brs. N.80°W., 11 lks. dist., marked T 6 S R 33 E S 19 B T. |
| | Land; hilly. |
| | Soil; 2nd rate. |
| | Densely covered with forests of pine, fir & tamarack, 80 chs. |
| | Thick undergrowth of balm and small pine, 80 chs. |
| | July 4th, 1883. |
| | E. on random line bet. Secs. 20 & 29. |
| | Var. 20°E. |
| | Descend over rolling ground, facing N. |