

## Exterior Lines, T 6 S R 34 E W M.

| Chains |  |
|--------|--|
|        | <p>A pine, 12 ins. diam., brs. S. 81° W., 30 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S B T.</p>  |
| 80.00  | <p>Set sandstone, 20 x 13 x 5 ins., 15 ins. in ground, for Cor.<br/>to Secs. 25, 30, 31 &amp; 36, marked with 5 notches on N.<br/>and 1 notch on S. edges; from which</p> <p>A pine, 10 ins. diam., brs. N. 36° E., 45 lks. dist.,<br/>marked T 6 S R 35 E S 30 B T.</p> <p>A tamarack, 12 ins. diam., brs. S. 52° E., 139 lks. dist.,<br/>marked T 6 S R 35 E S 31 B T.</p> <p>A pine, 10 ins. diam., brs. S. 30° W., 45 lks. dist.,<br/>marked T 6 S R 34 E S 36 B T.</p> <p>A fir, 18 ins. diam., brs. N. 70° W., 4 lks. dist.,<br/>marked T 6 S R 34 E S 25 B T.</p> |
|        | <p>Land; mountainous.<br/>Soil; 2nd rate.<br/>Densely covered with forests of pine, spruce, tamarack &amp;<br/>fir, 80 chs.<br/>Thick undergrowth of pine &amp; mountain balm.</p>   |
|        | <p>N. bet. Secs. 25 &amp; 30<br/>Var. 19<math>\frac{1}{2}</math>° E.</p>   |
| 25.75  | <p>Trail, course N.E. &amp; S.W.</p>   |
| 40.00  | <p>A pine, 12 ins. diam., which I mark <math>\frac{1}{4}</math> S on W. face, for <math>\frac{1}{4}</math><br/>Sec. Cor.; from which</p> <p>A pine, 10 ins. diam., brs. S. 69° E., 23 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S B T.</p> <p>A pine, 8 ins. diam., brs. N. 86° W., 11 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S B T.</p>  |
| 80.00  | <p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for<br/>Cor. to Secs. 19, 24, 25 &amp; 30, marked</p> <p>T 6 S S 19 on N.E.<br/>R 35 E S 30 on S.E.<br/>R 34 E S 25 on S.W. and<br/>S 24 on N.W. faces, with<br/>4 notches on S. and</p>   |