

Exterior Lines, T 6 S R 34 E W.M.

Chains

from which

A spruce, 10 ins. diam., brs. N.12°E., 8 lks. dist.,  
marked T 6 S R 35 E S 7 B.T.

A spruce, 10 ins. diam., brs. S.48°E., 9 lks. dist.,  
marked T 6 S R 35 E S 18 B T.

A spruce, 10 ins. diam., brs. S.32°W., 12 lks. dist.,  
marked T 6 S R 34 E S 13 B T.

A spruce, 10 ins. diam., brs. N.66°W., 10 lks. dist.,  
marked T 6 S R 34 E S 12 B T.

Land; mountainous.

Soil; 2nd rate.

Densely covered with forests of pine, fir & spruce, 80 chs.

N. bet. Secs. 7 & 12.

Var.19°40'E.

22.75 Creek, 6 lks. wide, runs N.E.

40.00 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for  $\frac{1}{4}$   
Sec. Cor., marked  $\frac{1}{4}$  S on W. face; from which

A fir, 5 ins. diam., brs. S.88°E., 10 lks. dist., marked  
 $\frac{1}{4}$  S B T.

A pine, 8 ins. diam., brs. N.76°W., 12 lks. dist.,  
marked  $\frac{1}{4}$  S B T.

51.75 Brook, 3 lks. wide, runs E.

77.00 " " " " " "

80.00 Set basalt stone, 13 x 12 x 10 ins., 8 ins. in ground, for  
Cor. to Secs. 1, 6, 7, & 12, marked with 1 notch on N.  
and 5 notches on S. edges; from which

A pine, 10 ins. diam., brs. N.52°E., 24 lks. dist.,  
marked T 6 S R 35 E S 6 B T.

A pine, 10 ins. diam., brs. S.12°E., 40 lks. dist.,  
marked T 6 S R 35 E S 7 B T.

A fir, 11 ins. diam., brs. S.62°W., 14 lks. dist.,  
marked T 6 S R 34 E S 12 B T.

A fir, 10 ins. diam., brs. N.33°W., 10 lks. dist.,  
marked T 6 S R 34 E S 1 B T.