

Exterior Lines, T 6 S R 34 E W.M.

Chains	<p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Densely covered with forests of pine, fir, spruce and tamarack, 80 chs.</p>
	<p>N. bet. Secs. 1 & 6,</p> <p style="text-align: right;">Var. 19°30'E.</p>
17.00	Brook, 3 lks. wide, runs E.
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face; from which</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., brs. S. 88°W., 7 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., brs. S. 81°E., 15 lks. dist., marked $\frac{1}{4}$ S B T.</p>
46.15	Spring, runs E.
62.54	<p>I intersect 1st Standard Parallel S., 12.68 chs. E. of $\frac{1}{4}$ Sec. Cor. on the S. Bdy. of Sec. 33, T 5 S R 34 E, at which point I</p> <p>Set post, 4$\frac{1}{2}$ ft. long, 4 ins. sq., 24 ins. in ground, for Closing Cor. to T 6 S R 34 & 35 E., marked</p> <p style="padding-left: 40px;">C C T 6 S on S.</p> <p style="padding-left: 40px;">R 35 E S 6 on E. and</p> <p style="padding-left: 40px;">R 34 E S 1 on W. faces, with</p> <p style="padding-left: 40px;">6 notches on S., E., & W. faces,</p> <p>from which</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., brs. S. 10°E., 20 lks. dist., marked T 6 S R 35 E S 6 B T.</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., brs. S. 50°W., 3 lks. dist., marked T 6 S R 34 E S 1 B T.</p> <p style="padding-left: 40px;">A pine, 8 ins. diam., brs. N. 70°W., 9 lks. dist., marked T 5 S R 34 E S 33 B T.</p>
	<p>Land; high & rolling.</p> <p>Soil; 2nd rate.</p> <p>Densely covered with forests of pine, fir, tamarack and spruce, 62.54 chs.</p>