

Subdivisional Lines, T 6 S R 34 E W M.

Chains

R 34 E S 25 on S.W.
 S 24 on NW. faces, with
 4 notches on N. and
 2 notches on S. edges;
 from which
 A pine, 10 ins. diam., brs. N.41°E., 14 lks. dist.,
 marked T 6 S R 35 E S 19 B T.
 A pine, 10 ins. diam., brs. S.24°E., 20 lks. dist.,
 marked T 6 S R 35 E S 30 B T.
 A pine, 10 ins. diam., brs. S.83°W., 5 lks. dist.,
 marked T 6 S R 34 E S 25 B T.
 A pine, 10 ins. diam., brs. N.33°W., 23 lks. dist.,
 marked T 6 S R 34 E S 24 B T.
 Thence I run
 N.89°39'W. on true line bet. Secs. 24 & 25, with same Var.
 39.85 Set pine, post, 3 ft. long, 3 ins. sq., 24 ins. in ground,
 for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on N. face; from which
 A pine, 10 ins. diam., brs. S.42°E., 12 lks. dist.,
 marked $\frac{1}{4}$ S B T.
 A pine, 6 ins. diam., brs. N.2°W., 3 lks. dist.,
 marked $\frac{1}{4}$ S B T.
 79.70 The Cor. to Secs. 23, 24, 25 & 26.
 Land; rolling.
 Soil; 2nd rate, except creek bottom, which is level with
 1st rate soil.
 Densely covered with forests of pine, fir, spruce & tamarack,
 79.70 chs.
 Undergrowth of huckleberry, small pine & laurel.

 N. bet. Secs. 23 & 24.
 Var. 20°E.
 Ascend.
 40.00 Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground,
 for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face; from which
 A pine, 13 ins. diam., brs. S.76°W., 18 lks. dist.,
 marked $\frac{1}{4}$ S B T.