

## Subdivisional Lines, T 6 S R 34 E W M.

Chains	
	A pine, 10 ins. diam., brs. N.42°W., 23 lks. dist., marked $\frac{1}{2}$ S B T.
46.00	Top of ridge, course N.E. & S.W. descended hillside facing N.W.
80.00	Set basalt stone, 14 x 8 x 8 ins., 9 ins. in ground, for Cor. to Secs. 11, 12, 13 & 14, marked with 4 notches on S. & 1 notch on E. edges; from which
	A fir, 8 ins. diam., brs. N.14°E., 25 lks. dist., marked T 6 S R 34 E S 12 B T.
	A fir, 12 ins. diam., brs. S.20°E., 20 lks. dist., marked T 6 S R 34 E S 13 B T.
	A fir, 8 ins. diam., brs. S.48°W., 21 lks. dist., marked T 6 S R 34 E S 14 B T.
	A fir, 12 ins. diam., brs. N.59°W., 7 lks. dist., marked T 6 S R 34 E S 11 B T.
	Land; hilly.
	Soil; 2nd rate.
	Densely covered with forests of pine & fir, 80 chs.
	July 21, 1883.

E. on random line bet. Secs. 12 &amp; 13.

Var. 19°40'E.

Ascend.

20.00	Enter high table land, course N.E. & S.W.
40.00	Set temp. $\frac{1}{2}$ Sec. Cor.
41.50	Trail, course N.W. & S.E.
42.20	Descend rocky bluff, course N.W. & S.E.
50.00	Foot of bluff, enter gentle slope.
71.00	Ravine, course N.E.
79.82	Intersect E. Bdy. of Tp. at 40 lks. N. of Cor. to Secs. 7, 12, 13 & 18, which is a post, 4 ins. sq., firmly set in ground, marked
	T 6 S S 7 on N.E.
	R 35 E S 18 on S.E.
	R 34 E S 13 on S.W. and
	S 12 on N.W. faces, with