

Subdivisional Lines, T 6 S R 34 E W M.

Chains

55.00 Ravine, course W.

80.00 Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground,
for Cor. to Secs. 22, 23, 26 & 27, marked
T 6 S S 23 on N.E.
R 34 E S 26 on S.E.
S 27 on S.W. and
S 22 on N.W. faces, with
2 notches on S. & E. edges;
from which
A pine, 6 ins. diam., brs. N.34°E., 5 lks. dist.,
marked T 6 S R 34 E S 23 B T.
A pine, 8 ins. diam., brs. S.29°E., 16 lks. dist.,
marked T 6 S R 34 E S 26 B T.
A pine, 8 ins. diam., brs. S.50°W., 7 lks. dist.,
marked T 6 S R 34 E S 27 B.T.
A pine, 5 ins. diam., brs. N.40°W., 5 lks. dist.,
marked T 6 S R 34 E S 22 B T.

Land; mountainous.
Soil; 2nd rate.
Densely covered with forests of pine, fir & tamarack, 80
chs.
Thick undergrowth of black pine & balm, 80 chs.

E. on random line bet. Secs. 23 & 26.
Var. 20°E.

20.00 Descend hill, course N. & S.

39.50 Foot of hill and ravine, course S.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

46.00 Top of small hill, course N.E. & S.W. and descend.

71.00 Top of hill & spring branch, 3 lks. wide, course S.W.
Ascend to

80.00 Intersect N. & S. line, 30 lks. N. of Cor. to Secs. 23, 24,
25 & 26
Thence I run
N. 89°47'W. on true line bet. Secs. 23 & 26.