

Subdivisional Lines, T 6 S R 34 E W M.

Chains	<p>2 notches on W. edges; from which</p> <p>A pine, 6 ins. diam., brs. N.72°E., 24 lks. dist., marked T 6 S R 34 E S 28 B T.</p> <p>A spruce, 12 ins. diam., brs. S.41°E., 27 lks. dist., marked T 6 S R 34 E S 33 B T.</p> <p>A spruce, 8 ins. diam., brs. S.52°W., 18 lks. dist., marked T 6 S R 34 E S 32 B T.</p> <p>A pine, 10 ins. diam., brs. N.24°W., 38 lks. dist., marked T 6 S R 34 E S 29 B T.</p> <p>Land; rolling, sloping N.</p> <p>Soil; 2nd rate.</p> <p>Densely covered with forests of pine, fir, tamarack & spruce, '80 chs.</p> <p>Thick undergrowth of huckleberry and balm, 80 chs.</p>
	<p>E. on random line bet. Secs. 28 & 33.</p> <p style="text-align: right;">Var. 19½°E.</p> <p>Gently ascending.</p> <p>35.00 " descend.</p> <p>40.00 Set temp. ¼ Sec. Cor.</p> <p>57.00 Descend hill, enter creek bottom, course N.E. & S.W.</p> <p>80.00 Intersect N. & S. line, 46 lks. N. of Cor. to Secs. 27, 28 33 & 34.</p> <p>Thence I run</p> <p>N.89°40'W. on true line bet. Secs. 28 & 33.</p> <p style="text-align: right;">With same Var.</p> <p>40.00 Set sandstone, 15 x 10 x 10 ins., 10 ins. in ground, for ¼ Sec. Cor., marked ¼ On N. face; from which</p> <p>A pine, 11 ins. diam., brs. S.29°W., 57 lks. dist., marked ¼ S B T.</p> <p>A pine, 10 ins. diam., brs. N.71°W., 66 lks. dist., marked ¼ S B T.</p> <p>80.00 The Cor. to Secs. 28, 29, 32 & 33.</p> <p>Land; rolling.</p> <p>Soil; 1st & 2nd rate.</p> <p>Densely covered with forests of black pine timber, 80 chs.</p>