

Subdivisional Lines, T 6 S R 34 E W M.

Chains

56.00 Ravine, course S.

73.00 Top of ridge, course S. and descend.

80.00 Intersect N & S. line, 36 lks. N. of Cor. to Secs. 15, 16,
21 & 22.

Thence I run
N.89°45'W. on true line bet. Secs. 16 & 21.

With same Var.

40.00 Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for
for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on N. face; from which
A pine, 12 ins. diam., brs. S.29°W., 40 lks. dist.,
marked $\frac{1}{4}$ S B T.
A pine, 8 ins. diam., brs. N.20°E., 43 lks. dist.,
marked $\frac{1}{4}$ S B T.

80.00 The Cor. to Secs. 16, 17, 20 & 21.

Land; mountainous.

Soil; 3rd rate.

Densely covered with forests of pine, fir & tamarack, 80 chs.
partly deadened by fire.

Thick undergrowth of willow, small pine & tamarack, 80 chs.

July 29, 1883.

N. bet. Secs. 16 & 17.

Var.20°E.

Descend to

7.00 Ravine, course W.

Ascending over rolling ground.

27.00 Trail, course N.E. & S.W.

40.00 Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground,
for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face; from which
A fir, 18 ins. diam., brs. N.50°W., 18 lks. dist.,
marked $\frac{1}{4}$ S B T.
A fir, 15 ins. diam., brs. N.65°E., 26 lks. dist.,
marked $\frac{1}{4}$ S B T.

Ascending gently to

70.00 Top of ascent and descend.