

Subdivisional Lines, T 6 S R 34 E W M.

Chains

Land; rolling.

Soil; 2nd rate.

Densely covered with forests of pine & fir, 75.40 chs.

Thick undergrowth of pine & fir, 75.40 chs.

Aug. 1, 1883.

N. bet. Secs. 29 & 30.

Var. 19°20'E.

1.50 Leave marsh, course E. & W.

Begin gradual ascent.

3.00 Mountain trail, course E. & W.

7.00 Spring branch, 4 lks. wide, runs S.E.

40.00 Set basalt stone, 12 x 8 x 8 ins., 8 ins. in ground, for  $\frac{1}{4}$

Sec. Cor., marked  $\frac{1}{4}$  on W. face; from which

A pine, 10 ins. diam., brs. N.70°W., 12 lks. dist.,  
marked  $\frac{1}{4}$  S B T.

A pine, 10 ins. diam., brs. N.30°E., 52 lks. dist.,  
marked  $\frac{1}{4}$  S B T.

Ascend.

65.00 Top of hill, enter gently rolling ground.

80.00 Set sandstone, 20 x 12 x 7 ins., 15 ins. in ground, for Cor.

to Secs. 19, 20, 29 & 30, marked with 2 notches on S. &  
5 notches on E. edges; from which

A tamarack, 10 ins. diam., brs. N.76°E., 25 lks. dist.,  
marked T 6 S R 34 E S 20 B T.

A pine, 6 ins. diam., brs. S.24°E., 25 lks. dist.,  
marked T 6 S R 34 E S 29 B T.

A tamarack, 10 ins. diam., brs. S.26°W., 18 lks. dist.,  
marked T 6 S R 34 E S 30 B T.

A pine, 10 ins. diam., brs. N.52°W., 23 lks. dist.,  
marked T 6 S R 34 E S 19 B T.

Land; hilly.

Soil; 2nd rate.

Densely covered with forests of pine, fir & tamarack, partly

burnt, 80 chs.  
Thick undergrowth of balm. 80 chs.