

## Subdivisional Lines, T 6 S R 34 E W M.

## Chains

Thence I run:

S.89°34'E. on true line bet. Secs. 7 &amp; 18.

With same Var.

- 35010 Set fir post, 3 ft. long, 3 ins. sq., 24 ins. in ground,  
for  $\frac{1}{4}$  Sec. Cor., marked  $\frac{1}{4}$  S on N. face; from which  
A tamarack, 12 ins. diam., brs. N.85°E., 17 lks. dist.,  
marked  $\frac{1}{4}$  SBT.  
A fir, 8 ins. diam., brs. S.57°W., 9 lks. dist.,  
marked  $\frac{1}{4}$  S B T.

75.10 The Cor. to Secs. 7, 8, 17 &amp; 18.

Land; mountainous.

Soil; 2nd rate.

Densely covered with forests of pine, fir & tamarack, 75.10  
chs.

Thick undergrowth of small pine, fir &amp; tamarack, 75.10 chs.

N. bet. Secs. 7 &amp; 8.

Var. 19°45'E.

Ascend.

- 22.50 Top of hill, course E. & W.  
40.00 Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground,  
for  $\frac{1}{4}$  Sec. Cor., marked  $\frac{1}{4}$  S on W. face; from which  
A pine, 10 ins. diam., brs. S.85°W., 18 lks. dist.,  
marked  $\frac{1}{4}$  S B T.  
A pine, 8 ins. diam., brs. S.63°E., 22 lks. dist.,  
marked  $\frac{1}{4}$  S B T.

55.00 Trail, course E. &amp; W.

Begin descent.

80.00 A point on hillside facing N.W. &amp;

Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground,  
for Cor. to Secs. 5, 6, 7 & 8, marked

T 6 S S 5 on N.E.

R 34 E S 8 on S.E.

S 7 on S.W. and

S 8 on N.W. Faces,