

Resurvey N.Bdy., T 7 S R 35 E W M.

Chains

it renders it necessary that a resurvey of this line should be made and a new set of Cors. established on which to close the subdivisions of T.7 S.,R 35 E.,making the N. Bdy. of Secs. 1 only 78.40 chs. in length.

N.89°39'W. on true line on N. Bdy. of Sec.4.

Var.20 $\frac{1}{4}$ °E.

80.00 Set basalt stone, 15 x 10 x 10 ins., 10 ins. in ground,for Cor. to Secs. 4 & 5, marked with 4 notches on E. and 2 notches on W. edges, from which

A pine, 40 ins. diam.,brs. S.18°E., 22 lks. dist., marked T 7 S R 35 E S 4 B T.

A fir, 24 ins. diam.,brs. S.56°W., 43 lks. dist., marked T 7 S R 35 E S 5 B T.

Land; high & rolling.

Soil; 2nd rate.

Densely covered with forests of pine, fir & tamarack,80 chs.

N.89°39'W. on true line on N. Bdy. of Sec. 5.

Var.20 $\frac{1}{2}$ °E.

1.59 The Cor. to Secs. 32 & 33, T 6 S R 35 E.

41.69 The $\frac{1}{4}$ Sec. Cor.

80.00 Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground,for Cor. to Secs. 5 & 6, marked T 7 S S 5 on S.E. & R 35 E S 6 on S.W. faces, with 5 notches on E. and 1 notch on W. edges, from which

A pine, 9 ins. diam.,brs. S.60°E., 14 lks. dist., marked T 7 S R 35 E S 5 B T.

A pine, 7 ins. diam.,brs. S.24°W., 30 lks. dist., marked T 7 S R 35 E S 6 B T.

Land;high & rolling.

Soil; 2nd rate.

Densely covered with forests of pine, fir & tamarack,80 chs.

N.89°39'W. on true line on N. Bdy. of Sec. 6.

Var.20 $\frac{1}{4}$ °E.