

Subdivisional Lines, T 6 S R 35 E W M.

Chains

A fir, 5 ins. diam., brs. S.45°W., 6 lks. dist.,
 marked $\frac{1}{4}$ S B T.

40.50 A trail, course N.E.

75.00 Summit of mountain, about 800 ft. above last Sec. Cor.

80.00 Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for
 Cor. to Secs. 17, 18, 19 & 20, marked

T 6 S S 17 on N.E.
 R 35 E S 20 on S.E.
 S 19 on S.W. and
 S 18 on N.W. faces, with
 3 notches on S. and
 5 notches on E. edges,

from which

A black pine, 8 ins. diam., brs. N.82°E., 26 lks. dist.,
 marked T 6 S R 35 E S 17, B T.

A fir, 10 ins. diam., brs. S.12°E., 17 lks. dist.,
 marked T 6 S R 35 E S 20 B T.

A B. pine, 6 ins. diam., brs. S.66°W., 22 lks. dist.,
 marked T 6 S R 35 E S 19 B T.

A fir, 6 ins. diam., brs. N.24°W., 36 lks. dist.,
 marked T 6 S R 35 E S 18 B T.

Land; mountainous, 80 chs.

Soil; 2nd rate.

Densely covered with forests of fir, pine & tamarack, 80 chs

E. on random line bet. Secs. 17 & 20.

Var. $20\frac{1}{4}$ °E.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

79.84 Intersect N. & S. line, 63 lks. N. of Cor. to Secs. 16, 17,
 20 & 21.

Thence I run

N.89°33'W. on true line bet. Secs. 17 & 20.

Var. $20\frac{1}{4}$ °E.

Descend about 200 ft. to

6.25 A brook, 4 lks. wide, runs N.

39.92 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$