

148 Surveyed for Wm. Prebster & Kelinears Bros. Nov. 26 1889
 By J.W. Kimbell County Surveyor Plat. No. 102

I Commenced at the Corner to Sec. 29=30=31		72 S 1/4 38 E W.M.	
Hence East var 20° E			
2000	Let Temporary 1/8 corner	Sec 30	Sec 29
4051	The 1/4 Sec corner bet Sec 29 & 32 from which I run west var 20° E		
20 1/2	Let Stone 6 x 10 x 84 inch for 1/8 corner	Sec 31	1/4 Sec
4051	The corner to Sec 29=30=31 & 32 Hence West var 20° E		22
2000	Let Temporary 1/8 corner	Sec 31	Sec 32
4051	The 1/4 Sec corner bet Sec 30 & 31 from which I run East var 20° E		
20 1/2	Let Stone 10 x 13 x 18 inch for 1/8 corner		
4051	The corner to Sec 29=30=31 & 32		

The corner to Sec 29=30=31 & 32
 Hence East var 20° E

2050 Let Temporary 1/8 corner
 4020 The 1/4 Sec corner bet Sec 20 & 29 from which
 I run west

2010 Set Post for 1/8 corner from which a Hawthorn 5 in db N 66° 2' 108"
 Hence South var 19° 30' E

8074 The 1/8 Corner on South Boundary S W 1/4 Sec 29
 The 1/8 corner on N Boundary N E 1/4 Sec 31
 Hence South var 20° E

10 00 Let Stake
 19 50 ditch
 20 00 Let Stake
 30 00 Let Stake
 40 00 Let Stake
 54 00 Plough mark & C
 55 58 Hand bound line to S S E lks a cross
 60 36 1/8 corner
 80 48 The 1/8 corner on South Boundary S E 1/4 Sec 31

J.W. Kimbell County Surveyor

149 Surveyed for John Henderson, Joe Harrison & S.W. Solau Dec 7 1889.
 By J.W. Kimbell County Surveyor Plat No. 103

I Commenced at the Corner to Sec 3=4=9 & 10		26 & 38 E W.M.	
from which a Pine 36 in db S 80° W 117 lbs " 44 " " N 83° W 198 " " 36 " " S 79° W 212 " " 36 " " N 48° E 234 " Hence South var 18° 30' E		Sec 4	Sec 3
2000	Let Temporary 1/8 corner		
39 25	The 1/4 Sec corner bet Sec 9 & 10 from which a Pine 15 in db N 42° E 131 lbs " 30 " " N 54° W 115 " from which I run North var 20° 10' E		
19 62 1/2	Set Post from which a Pine 20 in db N 57° E 66 lbs	Sec 9	Sec 10
39 25	The corner to Sec 9=10=5 & 4 Hence North var 19° 30' E		
15 00	Step Bluff 308 lbs to post on Wolf Creek Bottom		
2000	Let Temporary 1/8 corner		
23 75	Wolf Creek 15 db will		
24 75	Step Bank 20 feet high		
39 40	The 1/4 Sec corner bet Sec 3 & 4 from which a Pine 12 in db N 80° W 32 lbs " 20 " " S 60° E 48 " from which I run South var 20° E		
19 70	Set Post for 1/8 corner from which an alder 5 in db S 19° W 12 lbs " 5 " " N 81° W 2 1/2 lbs		
39 40	The corner to Sec 3=4=9 & 10 Hence West var 20° E		
2000	Let Temporary 1/8 corner		
49 76	Intersect 34 lbs North of 1/4 Sec corner bet Sec 4 & 9 from which a Pine 25 in db N 20° E 24 1/2 lbs a Tomrack 14 inch db S 5° E 43 lbs from which I run East		
2038	Let Post for 1/8 corner from which a Pine 5 in db S 29° E 182 lbs distant		
4076	The corner to Sec 3=4=9 & 10		

2000 Let Temporary 1/8 corner

23 75 Wolf Creek 15 db will

24 75 Step Bank 20 feet high

39 40 The 1/4 Sec corner bet Sec 3 & 4 from which
 a Pine 12 in db N 80° W 32 lbs
 " 20 " " S 60° E 48 " from which
 I run South var 20° E

19 70 Set Post for 1/8 corner from which
 an alder 5 in db S 19° W 12 lbs
 " 5 " " N 81° W 2 1/2 lbs

39 40 The corner to Sec 3=4=9 & 10
 Hence West var 20° E

2000 Let Temporary 1/8 corner

49 76 Intersect 34 lbs North of 1/4 Sec corner bet Sec 4 & 9
 from which
 a Pine 25 in db N 20° E 24 1/2 lbs
 a Tomrack 14 inch db S 5° E 43 lbs from which
 I run East

2038 Let Post for 1/8 corner from which
 a Pine 5 in db S 29° E 182 lbs distant

4076 The corner to Sec 3=4=9 & 10

Surveyed for John Anderson Joe Harrison & Solan Dec 7 1889

- The corner to Sec 3-4-9 & 10
Thence East var 20° E
- 20 00 Set Temporary 1/8 corner
- 40 70 The 1/4 Sec corner bet Sec 3 & 10 from which
I run west
- 20 35 Set Stake for 1/8 corner
- 40 70 The corner to Sec 3-4-9 & 10
The corner to Sec 2-3-34 & 35 on First Standard Parallel
Thence West on Standard line var 20° 15' E
- 40 00 Set Post for 1/4 Sec corner bet Sec 3 & 34
- 80 85 The corner to Sec 3-4-33 & 34 from which
a Pine 24 in dbh N 18° E 130 lbs
a Fir 20 " " N 75° W 35 "
a Pine 34 " " S 30° W 45 " from which
I run East var 20° 15' E
- 40 42 Post for the 1/4 Sec corner bet Sec 3 & 34
- 80 85 The corner to Sec 2-3-34 & 35
The 1/4 Sec corner bet Sec 3 & 10
Thence North var 20° E
- 12 50 Top of Bluff
- 18 00 Foot of Bluff
- 20 00 Set Temporary 1/16 corner
- 28 00 Wolf creek runs East
- 35 00 Clear creek runs S & E
- 40 00 Set Temporary 1/16 corner for center Sec 3
- 77 39 Intersect North Boundary 302 lbs East
of 1/4 Sec corner bet Sec 3 & 34 from which
I run South 2° 30' E
- 38 54 The center Sec 3 a Post in mound of rock from which
a Tomrack 12 in dbh N 18 1/2° W 75 lbs
- 57 94 The center 1/2 Sec 3 a Post for 1/16 corner
- 77 39 The 1/4 Sec corner bet Sec 3 & 10
The 1/4 Sec corner bet Sec 3 & 4
Thence East var 20° E
- 36 50 Clear creek runs S & E
- 39 24 The center Sec 3
- 82 34 Intersect East Boundary Sec 3 195 lbs North of 1/4 Sec corner
Thence East Thence West 40 60 lbs to center Sec 3

Surveyed for Joe Harrison John Anderson & Solan Dec 7 1889

- The 1/16 corner in center S 1/2 Sec 3
Thence West var 20° E
- 20 00 Set Temporary 1/16 corner
- 40 06 Intersect West Boundary 93 lbs South of 1/8 corner
on West Boundary S W 1/4 Sec 3 from which
I run East
- 20 08 Set Post for 1/16 corner in center S W 1/4 Sec 3 from which
a Fir 5 in dbh S 76° 30' W 65 lbs
- 40 06 The 1/16 corner in center S 1/2 Sec 3
The 1/4 Sec corner bet Sec 3 & 4
Thence West var 20° E
- 20 00 Set Temporary 1/16 corner for center E 1/2 Sec 4
- 23 50 Bluff 20 feet high
- 26 00 Clear Wolf creek 15 lbs wide runs S & E
- 28 00 Shingle creek runs N & E
- 40 00 Set Temporary 1/16 corner for center Sec 4
- 82 00 Intersect West Boundary Sec 4 100 lbs South of 1/4 Sec
bet Sec 4 & 5 from which
I run East
- 40 64 Center Sec 4
- 61 32 Set Stake for center E 1/2 Sec 4 from which
a Tomrack 5 inches North 85 lbs
- 82 00 The 1/4 Sec corner bet Sec 3 & 4
The 1/4 Sec corner bet Sec 4 & 33
Thence South var 21° E
- 20 00 Wolf creek
- 41 62 Intersect - S & W line 90 lbs West of Random State
- 61 63 Set Temporary 1/16 corner for center S 1/2 Sec 4
- 81 35 Intersect South Boundary 216 lbs East of 1/4 Sec corner
from which
I run North
- 19 86 Set Post for 1/16 corner in center S 1/2 Sec 4
- 39 72 Set Post for 1/16 corner in center Sec 4 from which
a Pine 9 in dbh S 9 1/2° W 20 lbs marked C.S.P.T.
a Fir 20 " " N 20° W 20 " " " C.S.P.T.
- 81 35 North Boundary Sec 4
The 1/8 corner on East Boundary S & 1/4 Sec 4
Thence West var 20° E
- 20 00 Set Temporary 1/16 corner
- 41 21 Intersect 7 lbs South of 1/16 corner in center Sec 4
Thence East var 20° E
- 20 60 Set Post for 1/16 corner in center S 1/2 Sec 4
a Tomrack 6 in dbh N 70° E 25 lbs - W Kimbrell County Surveyor