

80.00 To a Pine tree, 8 in. in diam,  
mkd. T1N R34E S2 on NE  
S11 on SE S10 on SW S3 on NW  
faces, with 5 notches on S x 2 on  
east edges for cor 2, 3, 10, 11.

10" Pine bears N4°E 10 lbs.

mkd S2 T1N B.T.

20" Pine bears N45°W 25 lbs mkd

S3 BT

16" Pine bears S32°W 8 lbs mkd

S10 BT.

10" Pine bears S3°E 7 lbs mkd

S11 R34E B.T.

S 89°-33'W bet sec. 2 & 11

40.02 Post 3"x3"x3'-0" 24 in ground

mkd  $\frac{1}{4}$  S on N. 18" Pine bears

S50°E 10 lbs mkd  $\frac{1}{4}$  S B.T.

16" Pine bears N10°W 77 lbs

marked  $\frac{1}{4}$  S B.T.