

80.35 to cor Secs 4, 5, 8, 9.

North bit secs. 19 & 20

80.00 Post 4x4x48"-24" in the ground  
 cor to Sec 17, 18, 19, 20 mtd.  
 TIN S17 on NE, R34E S20 on  
 SE, S19 on SW, S18 on NW faces  
 with 5 notches on E edge & 3 on S edge  
 from which a pine 20" in dia bears  
 N 45° E 50 lbs mtd S17 TIN B.T.  
 24" Pine bears N 10° W 83 lbs mtd  
 S18 B.T. 10" Pine bears S 32° W  
 150 lbs mtd S19 B.T. 20" Pine  
 bears S 5° W 57 lbs mtd S 20  
 R 34 E B.T.

N 89° 43' W bit sec 17 & 20 var 19° E

40.29 Post 3x3x36"-24" in ground  
 mtd  $\frac{1}{4}$  S on N face from which  
 a 30" Pine bears N 15° E 150 lbs