

chains.

1.8

4

5

North lect. sects 13 & 14. var. $24^{\circ}30'E$

14.50 Gulch, course W

25.00 Summit of ridge course W.

40.00 Post, $3" \times 3" \times 3'$; 2' in ground. mkd $\frac{1}{4}S$ on W face. Pine tree 7 in dia bears $N75^{\circ}E$ 47 lbs mkd $\frac{1}{4}B.T.$

Pine 5" dia bears $N76^{\circ}W$ 75 lbs, mkd $\frac{1}{4}S.B.T.$

48.50 A gulch course W.

80.00 Post $4" \times 4" \times 4'0"$, 2' in ground mkd. TIN R34E S12 on NE

S11 on NW, S14 on SW S13 on SE.

mkd with 1 notch on E & 4 on 3 edges.

A 20" Fir bears $N25^{\circ}W$ 16 lbs.

mkd TIN R34E S11 B.T.

24" pine bears $S70^{\circ}E$ 28 lbs,

mkd S13 B.T.

6" fir $N53^{\circ}E$ 30 lbs mkd S12 B.T.

Mounds of stone around post.