

38 37 Sub. T. 1 NR 34 E.

Oct. 10 Cov of Secs 4, 5, 32 + 33 on N bdy 1-34 is a basalt
24 x 14 x 12 ins above ground in mound of
stone, marked H on west 11111 on S.

I mark 1111 on E. Thence South

bet. secs. 4 + 5 (on W. 42 lbs. N.)
21.06 Set temp $\frac{1}{16}$ cov.

(84 lbs. short)
40.22 Interest $\frac{1}{4}$ cov. cor. a post marked $\frac{1}{4}$ S. set
(41.06) bins in ground. Fix 20 N 22° W. 27 lbs. (29)
Fix 30 S 18° E 130 lbs. (80)

Marks overgrown. I cut into these trees about
6 inches to uncover marks.

Thence South (From pt. 10 lbs. W. of $\frac{1}{4}$ cov.)

20. Set temp $\frac{1}{16}$ cov. (Correction 1 lb. N. + 2 lbs. W.)
1 lb. N of fence cor. beam. S + W. + E. 7 lbs. W.

89.98 Fall 24 lbs. E. of cov pt. for cov of Secs 4, 5, 32.
at fence corner. N + W

From $\frac{1}{4}$ cov bet secs 4 + 9 run N through Sect
20. Set temp $\frac{1}{16}$ cov. Correction 1 lb. W. 2 lbs. S.

40.04 Interest E + W true line through center
Sec. 4. Correction 2 lbs. W.
Phence Continue North

0.39 Interest
E + W random line. 32 lbs. W. of temp
stake set 40 lbs. W. of $\frac{1}{4}$ cov bet secs. 3 + 4
Correction 2 lbs. W.

20.00 Set temp $\frac{1}{16}$ cov. (Correction $4\frac{1}{2}$ lbs. W. $9\frac{1}{2}$ lbs. S.)

20.40 a post 6 ins diam. 4 ft. above ground. bears E 25 lbs.

40.34 Fall 4 lbs E. of $\frac{1}{4}$ cov. bet secs 4 + 33

Oct (40.53) a basalt 9 x 7 x 6 ins. set 2 in in ground,
19/10 marked $\frac{1}{4}$ on N. face, not witnessed
17