

41.06
.74
40.22

38
38

N bdy TINR 34 E

- 10/11/17 From cor of 4.5, 32 & 33 run N 89° 58' E
20. Set temp 1/16
23. Fence N 20° W
- HO. Intersect 1/4 cor bet secs 4 & 33. a stone with
(N 71° E) Pine Stump 24 N 71° E 255, marks nearly obliterated 294
Thence N 89° 58' E Pine stump 24 S 77° E, near BT
14.00 gulch N 20° W. (S 75° E)
- 20.00 Set temp 1/16 cor on steep N E slope, near small fir with
[top cut off]
- 28.50 Cottonwood gulch, NW, acc.
- HO. No trace of cor of secs. 3, 4, 33 & 34. Set temp cor
Continue East on same line
- 79.70 1/4 cor bet secs 3 & 34 bears N. 76 lbs.

Surf TINR 34 O

- From temp. cor of secs. 3, 4, 33 & 34 on N bdy
run South 45° W.
- 9:00 Cottonwood gulch with creek 1/4 mile NW,
just below forks, where gulch enters from E
- 20 Set temp 1/16 cor.
- 40.46 Fall 75 lbs. E. of 1/4 cor bet secs 3 & 4
- From 1/16 cor. 20 chs S. of 1/4 cor bet secs 3 & 4 run W
- 19.50 Set temp 1/16 cor. (Cor. 66 lbs. W, in road)
- 40.32 Intersect 1/16 cor. 20 chs N of 1/4 cor bet secs 4 & 9
Thence continue West
- 20.08 Set ~~temp~~ 1/16 cor (Cor 1 lb S, 8 lbs W.)
- 40.16 Fall 21 lbs. N of 1/16 cor

10-11-17