

Sub T 1 N R 3 H E

Oct. 24 From 1/4 cor bet sec. 6 + 7 run North through sec. 6

20. Set 1/16 cor - (20 lks S)  
29 gulch NW. spring about 4 chos E  
39.60 Intersect 0, sec. 6.

Thence north, 15 lks N  
Set 1/16 cor - (15 lks N) \$48.00 Spring bears W about 2 chos  
40.42 Intersect 1/4 cor bet sec 6

(40.12) From 1/4 cor bet sec 5 + 6 run East

21 Set 1/16 cor.

40 Set 1/4 cor at center Sec. 5, Oct 18, 1917  
From 1/4 cor bet 4 + 5 run West 4 miles

20. Set 1/16 cor  
40.14 Intersect N + S center line, 18 lks S. of temp 0 with S 40 lks S. of temp. 0 set from W. and continue W.  
Intersect 1/4 cor bet 5 + 6,

From cor of 5, 6, 7 + 8 run N bet 5 + 6

20 Set 1/16 cor, (3 lks S)

39.94 Intersect 1/4 cor

Thence North

15. Fence N W + N 70° E

20 Set 1/16 cor. (7 lks S, 7 lks E.)  
(40.25)

40.39 Cor of sec 5, 6, 31 + 32 bears E. 14 lks

Sub T 2 N R 3 H E

From cor of 5, 6, 31 + 32 on S. body run N bet, sec. 31 + 32

Gulch NW

Set 1/16 cor - 38.00 old fence N 35° W  
12. 20. 39.44 1/4 cor bet sec 31 + 32 bears W, 88 lks. (Ridge)

Thence by B.S. to cor of sec 5, 6, 31 + 32